

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-039-20063-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1968

CONSERVATION DIVISION
Wichita, Kansas

10-28-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Norman D. Fitzgerald,

Complete Address: Box #5046, Abilene, Texas. 79605

Lease Name Slim Macy Well No. 1

Location NW-SW Sec. 14 Twp. 1 Rge. (E) (W) 29

County Decatur Total Depth 2815'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: Lost circulation in this well @ 2115' and after repeated attempts to regain same abandoned well.

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza Building, Wichita, Ks. License No.

Operation Completed: Hour 11:00AM Day 26 Month 10 Year 1968

The Above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 200 Sx.

Ran DP to 1475' and set 25 Sx. HA-5 "Hot" cement in an attempt to shut off loss. Let set for 2 hours and attempted to fill hole with fluid but top of fluid remained @ 340'.

Pushed wooden plug to 1475' with DP and ran 1 1/2 yards of crushed rock on top of wooden plug. Ran measuring line and found top of bridge @ 900'. Ran 80 Sx. cement @ 900',

pulled DP to 275' and displaced 40 Sx. cement @ 275'. Hole circulated. Pulled DP, set bridge @ 30' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Dehals*
Well Plugging Supervisor

INVOICED

DATE 10/28/68

INV. NO. 8699-11