

15-039-20146-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rosen Oil Corporation,

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name Templeton Well No. B-1

Location CNE-SW Sec. 32 Twp. 1 Rge. (E) (W) 29

County Decatur Total Depth 3940'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Ks. License No.

Operation Completed: Hour 4:15 PM Day 16 Month 11 Year 1970

The above well was plugged as follows:

230'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1350' and displaced 100 Sx. cement thru
DP from 1350' to 1025'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED RECEIVED
STATE CORPORATION COMMISSION

DATE 11-25-70 NOV 25 1970 11-25-1970

INV. NO. 2915-4 CONSERVATION DIVISION
Wichita, Kansas