

15-039-20187-00-00

Form CP-3  
Rev. 6-4-68

*[Handwritten mark]*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-2-1970

Operator's Full Name Empire Drilling Company,  
Complete Address 650 Fourth National Bank Building, Wichita, Kansas.  
Lease Name Macy Well No. B-1  
Location SE-SE-NW Sec. 11 Twp. 1 Rge. (E) (W) 29  
County Decatur Total Depth 4152'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A I  
Other well as hereafter indicated       
Plugging Contractor Murfin Drilling Company,  
Address 617 Union Center Building, Wichita, Kansas. License No.       
Operation Completed: Hour 1:00 PM Day 28 Month 10 Year 1970

The above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1200'.  
Circulated hole with heavy mud. Pulled DP to 1425' and displaced 100 Sx. cement thru  
DP from 1425' to 1100'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 11/2/70  
INV. NO. 2790-W