

15-039-20027-00-00

Form CP-3  
Rev. 6-9-67

KANSAS

*24*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

NOV 2 1967

11-2-1967

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Company.

Complete Address 1130 Wichita Plaza, Wichita, Kansas.

Lease Name Moore Well No. A-1

Location SE-SE-SE Sec. 2 Twp. 1 Rge. (E) (W) 29

County Decatur Total Depth 2396

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.       

Operation Completed: Hour 7:00AM Day 28 Month 10 Year 1967

The above well was plugged as follows:

251'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
Dakota section from 1575' to 1400'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 100 Sx. cement  
thru DP from 1600' to 1280'. Pulled DP to 260' and displaced 20 Sx. cement thru DP.  
from 260' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Dehls*  
Well Plugging Supervisor

DATE 11/2/67  
INV. NO. 6612-4