

15-039-20222-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1971
CONSERVATION DIVISION
Wichita, Kansas
11-8-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Excalibur Production Company,

Complete Address 523 West Kansas, McPherson, Kansas.

Lease Name Frank J. Ploussard Well No. 1

Location NE-NW-NW Sec. 5 Twp. 1 Rge. (E) (W) 29

County Decatur Total Depth 3870'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Helberg Oil Company,

Address Box #32, Morland, Kansas. License No.

Operation Completed: Hour 3:00 AM Day 4 Month 11 Year 1971

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1175'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: K. L. Nichols
Well Plugging Supervisor

DATE 11-11-71

INV. NO. 4632-W