

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
12-11-1973
DEC 11 1973
CONSERVATION DIVISION
Wichita, Kansas

15-039-20276-00-00

Operator's Full Name Empire Drilling

Complete Address 650 4th Nat'l Bk Bldg., Wichita, Kansas

Lease Name Anderson Well No. 1

Location A/ SE SE SE Sec. 25 Twp. 1 Rge. (E) (W) 30

County Decatur Total Depth 3810'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 3 P Day 9 Month 12 Year 1973

The above well was plugged as follows:

RTD 3810' 8 5/8 csg set at 170' ewe 150 sk. Cem. Mat. 50-50 pez 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 1500' and displaced 70 sk
cem thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cem
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/11/73

INV. NO. 8283-42

Signed: Leo J. Mussey
Well Plugging Supervisor