

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
06-29-1967  
JUN 29 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-039-20014-00-00

Operator's Full Name W. W. Sauvage,

Complete Address: 106 So. Rodhauer, Oberlin, Kansas. 67749

Lease Name Demmer Well No. 1

Location NW-NW-SE Sec. 30 Twp. 1 Rge. (E) (W) 30

County Decatur Total Depth 4410'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Sauvage Drilling Company, Incorporated,

Address: 106 South Rodhauer, Oberlin, Kansas. License No.     

Operation Completed: Hour 3:00AM Day 27 Month 6 Year 1967

The Above well was plugged as follows:

209'--8 5/8" Surface pipe, cement circulated with 150 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 220', set plug and displaced 20 Sx. cement

thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement

to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/29/67

INV. NO. 5487-W

Signed: N. R. Dehler  
Well Plugging Supervisor