

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-00534-00-00
Spot: CE2E2NW Sec/Twnshp/Rge: 11-1S-27W
3960 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: WARNER UNIT Well Number: 302
County: DECATUR Total Vertical Depth: 3400 feet

Operator License No.: 31660 Conductor Pipe: Size feet:
Op Name: ENERGY SEARCH OPERATING COMPAN Surface Casing: Size 8.625 feet: 256 225 SX CMT
Address: P.O. BOX 31697 Production: Size 5.5 feet: 3370 250 SX CMT
AURORA, CO 80041 Liner: Size feet: #110.50

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/13/2001 10:00 AM
Plug Co. License No.: 31660 Plug Co. Name: ENERGY SEARCH OPERATING COMPANY
Proposal Rcvd. from: RAYMOND DOROTHY Company: ENERGY SEARCH OPERATING CO Phone: (308) 375-4344

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/13/2001 11:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:
8 5/8" set at 256' w/225 sxs cwc. 5 1/2" set at 3370' w/250 sxs.
Prod.Perfs 3175' - 3296'. P.BTD 3290'.
Squeezed 5 1/2" w/220 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 500#. S.I.P. 300#.
Squeezed 8 5/8" w/30 sxs cement to Max. P.S.I. 100#.
Plug complete.

Remarks: LEASE ALSO KNOWN AS REDMAN #2. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Carl Goodrow

RECEIVED
SEP 26 2001
KCC WICHITA

(TECHNICIAN)
INVOICED
DATE 9-26-01
-NO. NO. 2002060638

SEP 20 2001

D G HANSEN

#2 REDMAN

11-1-27W
E2 E2 NW

Contr. C-G DRLG

DECATUR

County

E. 2499R B Comm. 3-11-57 Comp. 5-3-57 IP 38 BOPD/LANS

PHY POT.

Tops	Depth	Datum
ANH	1855	644
HOW	2897	-398
SEV SND	2976	-477
TOP	3002	-503
HEEB	3121	-622
TOR	3145	-646
LANS	3160	-661
B/KC	3377	-878
TD	3400	-901

Casing
 8" 256
 5" 3370
 DST 3162-88/1 HR, 15' MDY 0, 30' OCM, BHP 930#
 DST 3193-3225/30", 20' M, BHP 120#
 DST 3218-65/30", 20' M, BHP 540#
 BST 3262-3300/1 HR, 15' MUD, BHP 90#
 DST 3295-3330/1 HR, 25' M, TR 0, BHP 1770#
 DST 3327-60/50", 6' M, BHP 0#
 DST 3368-3400/30", 10' M, BHP 75#
 PERF 3279-86, 3247-59, 3203-11, 3194-99
 WARNER POOL
 3175-81, 3163-70
 ACID 4000

+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS