

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20513-00-00
Spot: NWSESW Sec/Twnshp/Rge: 22-12S-21W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BAUGHER Well #: B-1
County: TREGO Total Vertical Depth: 3970 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

PROD Size: 4.5 feet: 3966 150 SX CMT
SURF Size: 8.625 feet: 138 110 SX CMT

#129⁰³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2004 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 250 sxs cement and 400# hulls.
Perfs at 925' - 1675' - 2200'.

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL
Date/Time Plugging Completed: 04/08/2004 2:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Sanded wellbore to 3900' with 4 sxs cement.
Shot pipe off at 600' - decided to leave in the hole.
Ran tubing to 2225' - pumped 75 sxs cement with 300# hulls.
Pulled tubing to 1000' - circulated with 75 sxs cement and 100# hulls.
Pulled all tubing and squeezed with 25 sxs cement to Max. P.S.I. 200#.
Tied to 4 1/2" x 8 5/8" annulus - squeezed 75 sxs cement.
Max. P.S.I. 200#. S.I.P. 150#.
Total of 250 sxs 60/40 pozmix - 10% gel and 400# hulls.

RECEIVED
APR 16 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3951	3956		

Remarks: COPELAND ACID CEMENT COMPANY. AMERICAN TANK-WATER.

Plugged through: TBG

District: 04

Signed Roger Moses
(TECHNICIAN)

INVOICED
DATE 4-16-04
INV. NO. 2004061431

APR 12 2004

