

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-00522-00-00  
Spot: CSWSWNE Sec/Twnshp/Rge: 11-1S-27W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: SATER Well Number: 1  
County: DECATUR Total Vertical Depth: 3418 feet

Operator License No.: 31660

Conductor Pipe: Size feet:

Op Name: ENERGY SEARCH OPERATING COMPAN

Surface Casing: Size 8.625 feet: 320

Address: P.O. BOX 31697  
AURORA, CO 80041

Production: Size 5.5 feet: 3418

Liner: Size feet:

\$ 111.09

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/23/2001 9:00 AM

Plug Co. License No.: 31660

Plug Co. Name: ENERGY SEARCH OPERATING COMPANY

Proposal Rcvd. from: RAY DOROTHY

Company: ENERGY SEARCH OPERATING CO Phone: (303) 344-2067

Proposed Plugging Method: Order 260 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/23/2001 10:15 AM

KCC Agent: CARL GOODROW

**Actual Plugging Report:**

8 5/8" set at 320' w/250 sxs cwc. 5 1/2" set at 3418' w/200 sxs.  
PBTD 3402'. Perfs. 3186' - 3236'. Exempt area.  
Squeezed 5 1/2" w/265 sxs cement blend with 500# hulls mixed in to Max. P.S.I. 1000#. Held.  
Squeezed 8 5/8" w/15 sxs to Max. P.S.I. 500#+. Blew out head.  
Plug complete.

**INVOICED**

DATE 6-6-01

TRK. NO. 2001061888

**RECEIVED**

KANSAS CORPORATION COMMISSION

JUN 6 2001

Remarks: LEASE ALSO KNOWN AS WARNER UNIT 101. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

MAY 30 2001

CITIES SERVICE

#1 SATER

11-1-27W  
SW SW NE

Contr. LOHMANN-JOHNSON

DECATUR

County

E 2531

Comm.

Comp.

8-17-56

IP 497 BOPD/LANS


Tops	Depth	Datum
HOW	2923	- 392
TOP	3027	- 496
HEEB	3150	- 619
DOD	3174	- 643
LANS	3193	- 662
B/KG	3402	- 871
TD	3420	- 889

Casing

8" 320

DST 2924-3000/1 HR, 35' M, BHP 790#  
 DST 3112-60/1 HR, 48' M, BHP 945#  
 DST 3194-3253/1 HR, 245' V H OCM, 180'  
 BLACK O, BHP 1055#  
 DST 3276-3328/1 HR, 110' MDY SW, BHP  
 850#  
 DST 3350-93/1 HR, 20' MUD, BHP 60#  
 PERF 33/3306-14: 41/3186-96: 37/3227-  
 36: ACID 7000, PMP 9 BOPH, 18% WTR

Warner Pool



INDEPENDENT OIL & GAS SERVICE ✓  
 WICHITA, KANSAS