

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05380-00-00
Spot: NENESE Sec/Twnshp/Rge: 28-13S-17W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: SOPHIA DREILING Well #: 1
County: ELLIS Total Vertical Depth: 3507 feet

Operator License No.: 5145
Op Name: DREILING OIL INC
Address: PO BOX 550 1008 CODY AVE
HAYS, KS 67601

PROD Size: 5.5 feet: 3482 150 SX CMT
SURF Size: 8.625 feet: 90 75 SX CMT

98
113

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2004 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: DREILING OIL, INC. Phone: (785) 625-8327

Proposed Plugging Method: Emergency plug.
Ordered 225 sxs cement and 500# hulls.
Casing egged at 628'.
Perfs at 600' - 1200' - 1825'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2004 11:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 870' - spotted 70 sxs cement to circulate.
Pulled all tubing - squeezed 5 1/2" casing with 100 sxs cement.
Max. P.S.I. 500#. S.I.P. 100#.
Tied to 8 5/8" x 5 1/2" annulus - squeezed 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 100#.
Total of 195 sxs 60/40 pozmix - 10% gel.

Perfs:

Top	Bot	Thru	Comments
3507	3585		
3418	3420		
3401	3403		
3325	3327		
3306	3308		
3263	3265		
3212	3214		

RECEIVED
APR 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. STEWART TANK-WATER.

Plugged through: TBG

District: 04

Signed

Roger L Moses

(TECHNICIAN)

INVOICED

DATE

4-16-04

INV. NO.

2004061424

Form CP-2/3

APR 12 2004

APR 1959

OWLE

Sept 28-13-17W 34
INVOICED

GLENN NYE #1 DREILING NE NE SE

Contr. _____ ELLIS County

E. 1959RB Comm. _____ Comp. 5-30-52 IP 518 BOPD (ARB)
PHY POT

Tops	Depth	Datum
Awk	1168~	+791
HEEB	3195	-1236
LANS	3236	-1277
B/KC	3470	-1511
ARB	3481	-1522
T.D.	3507	-1548

Casing
 5" 3482 DST 3256-62, 45 MIN,
 35" SL OIL CUT
 MUD:
 DP: 32 BOPH

SUGARLOAF SE POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS