

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-05164-00-00
Spot: SENWNE Sec/Twnshp/Rge: 17-1S-34W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: CAHOJ UNIT Well #: 32
County: RAWLINS Total Vertical Depth: 4310 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 4288 w/250 sxs cmt
SURF Size: 8.625 feet: 450 w/300 sxs cmt

140⁰⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2004 9:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-6781

Proposed Plugging Method: Ordered 275 sxs Midcon II Cement and 750# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 04/08/2004 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

CIBP at 4022'. TD & PBTd at 4022'. Top of cement at 2750'.
8 5/8" S.P. at 450' w/300 sxs cement. 5 1/2" production casing set at 4288' w/250 sxs cement.
Ran tubing to 2500' - pumped 125 sxs cement with 400# hulls.
Pulled tubing to 1200' - pumped 60 sxs cement with 350# hulls. Cement to surface.
Connected to 5 1/2" production casing - pumped 10 sxs cement.
Max. P.S.I. 400#. S.I.P. 100#.
Connected to 8 5/8" surface casing - pumped 30 sxs cement.
Max. P.S.I. 400#. S.I.P. 250#.

Perfs:

Top	Bot	Thru	Comments
3992	3998		
3975	3986		
3870	3874		
3593	3600		
3554	3558		

RECEIVED
APR 16 2004
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS CAHOJ A. S. #3. SWIFT SERVICES, INC. - TICKET #6396.

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

INVOICED

DATE 4-16-04
INV. NO. 2004061426

Form CP-2/3

APR 09 2004

17-1-34W
 SE NW NE
 #3 A S. CAHOJ
 CLAUDE WENTWORTH
 3101
 11-27-59
 3000 BOPD

SKELLY OIL CO

#3 A S. CAHOJ

17-1-34W

SE NW NE

Contr. CLAUDE WENTWORTH

RAWLINS County

E 3101 Comm. Comp. 11-27-59 IP 3000 BOPD

Tops	Depth	Datum	Casing
ADM	3604	-503	8" 450 5" 4288 DST 3972-4000/1 HR, 40' H OCM, BHP 1070#
TOP	3774	-673	DST 4010-43/1 HR, 5' M, F SPKS 0, BHP 35#
OREAD	3876	-775	DST 4162-90/1 HR, 3240' 0, NW, BHP 1220#
LEAV	3922	-821	PERF 32/4209-17: ACID 250: 103 BO/2 HR & 3 BWP: PLUG 4190: 28/4171-78: 3400' 01H/1
LANS	3970	-869	HR: SWB 110 BO/2 HR: PLUG 4150: 24/4126-32: SWB 3 BO & 15 BW/4 HR: SWB 1 1/2 BO & 3 BW/2
B/KC	4242	-1141	HR: SQZ: 52/4079-90: ACID 250: SWB 3 BO & 57 BW: SQZ: 32/4026-34: SWB 5 BO & 12 BW/4
MARM	4276	-1175	HR: SQZ: 44/3975-86: 24/3992-98: ACID 250: SWB 2 GO, TR W/1 HR: ACID 1250: SWB 6 BO & 1 BW/2 HR: REPERF 32/4209-17: ACID 500: SWB 20 BO & 1/2 BW/2 HR: REPERF 28/4171-78: ACID 500: SWB 34 BO & 2 BW/2 HR
TD	4310	-1209	

CAHOJ POOL

INDEPENDENT OIL & GAS SERVICE,
WICHITA, KANSAS