

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02167-00-01  
Spot: NENESW Sec/Twnshp/Rge: 9-10S-25W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BELLERIVE Well #: 1  
County: GRAHAM Total Vertical Depth: 4060 feet

Operator License No.: 32705  
Op Name: RANEY OIL COMPANY, LLC  
Address: 3425 TAM O'SHANTER  
LAWRENCE, KS 66047

PROD Size: 4.5 feet: 4167 200 SX CMT  
SURF Size: 8.625 feet: 215

*\$ 131<sup>95</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/08/2004 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered 225 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/08/2004 2:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Sanded bottom to 3760' w/4 sxs cement.  
Shot pipe off at 1575' - pulled to 1370' - pumped 70 sxs cement with 200# hulls.  
Pulled casing to 500' - pumped 30 sxs cement with 100# hulls.  
Pulled casing to 200' - circulated with 50 sxs.  
Pulled all but one joint of casing and topped off with 20 sxs cement.  
Pulled last joint of casing - cellar full of cement.  
Total of 170 sxs 60/40 pozzmix - 10% gel and 400# hulls.

Perfs:

Top	Bot	Thru	Comments
4017	4020		
3997	4004		
3978	3980		

RECEIVED  
APR 16 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. KELLER TANK-WATER.

Plugged through: CSG

District: 04

Signed

*Roger A. Moses*  
(TECHNICIAN)

INVOICED

DATE

*4-16-04*

INV. NO.

*2004061428*

Form CP-2/3

APR 12 2004

RANEY OIL CO LLC  
LAWRENCE KS 66047

9-10S-25W  
NE NE SW

#1 BELLERIVE OWWO

**WABIC FT**

site 1/4 N & 1-1/2 W OF ST PETER KS  
cont: MURFIN DRILLING #S  
geol: ROGER WELTY

API 15-065-02157  
#sc ELRICK


fr date 05/19/2003    sup date 05/30/2003    chg date 06/09/2003    corr issued 10/06/2003    last revised 10/06/2003

ELV: 2539 KB, 2533 GL SMP  
 tops ..... depth/datum  
 ANH ..... 2165 +374  
 HEEB ..... 3777 -1238  
 TOR ..... 3801 -1262  
 LANS ..... 3819 -1280  
 PSTD ..... 4046 -1507  
 LTD ..... 4047 -1508  
 BKC ..... 4050 -1511  
 RTD OLD ..... 4060 -1521

IP status  
 OIL, P 1.5 BO & 3.5 BWPD, LKC 3978-4020 OA, 06/20/2003  
 OLD INFO: OPERATOR WAS COOPERATIVE REFINERY  
 ASSOC, 1 BILLINGER A, SPD 10/19/1957, 10/31/1957 8-5/8"  
 215 (ALT 2), D&A, PENN, 10/31/1957(CARD ISSUED  
 11/08/1957)  
 CONTR: COOPERATIVE REFINERY ASSOC  
 COMMENT: WAS TEMP API IOG-20472  
 NO CORES  
 DST (1) 3786-3810 (TOR), / OP 60", REC 53' M, REMARK: FP  
 NA ISIP 1125#

RANEY OIL CO LLC  
LAWRENCE KS 66047

9-10S-25W  
NE NE SW

#1 BELLERIVE OWWO

DST (2) 3810-3830 (LANS), / OP 60", REC 9' OIL SPKD M, REMARK: FP NA ISIP 50#  
 DST (3) 3896-3916 (LKC), / OP 60", REC 657' W, REMARK: FP NA ISIP 1200#  
 DST (4) 3947-3963 (LKC), / OP 60", REC 24' M, REMARK: FP NA ISIP 0#  
 DST (5) 3968-4007 (LKC), / OP 60", 330' GIP, REC 110' OIL & GCM, REMARK: FP NA ISIP 1060#  
 DST (6) 4010-4034 (LKC), / OP 60", REC 58' V SLI OIL & GCM, REMARK: FP NA ISIP 170#  
 DST (7) 3836-3854 (LKC, W/STR PKR), / OP 60", REC 2040' SW, REMARK: FP NA ISIP 1245#  
 NEW INFO: FR 05/19/2003, RE-ENTERED 05/30/2003 WSH DWN TO 4060, GRN LOG RUN DC  
 06/09/2003 CSG: SET 4-1/2" 4167 / 200 SX, MULTI STAGE COLLAR AT 2169.  
 COMMENT: KCC API 15-065-02167-0001  
 TRGT ZN: LKC (OIL), PTD 4060 (LKC), MICT - CO, PB 4046, PF (KC) 4017-4020, W / 4 SPF, AC 500 GAL  
 (15%), SWB LD, SO, PF (KC) 3997-4004, W / 4 SPF, AC 500 GAL (15%), SWB LD, SO, PF (KC) 3978-3980,  
 W / 4 SPF, AC 500 GAL (15%), SWB LD, SO, SET 2-3/8" TBG AT 4150, NO PKR, POP, IPP 1.5 BO & 3.5  
 BWPD (GR 36), GTSTM, DOFP 6/20/2003, COMMINGLED