

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23662-00-00
Spot: S2SESE Sec/Twnshp/Rge: 6-11S-16W
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: CHESNEY Well #: 2
County: ELLIS Total Vertical Depth: 3575 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

PROD Size: 5.5 feet: 3574 225 SX CMT
SURF Size: 8.625 feet: 222 225 SX CMT

116' 19

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2004 2:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 18 sxs gel.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2004 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Annulus full of cement.
Swaged onto 5 1/2" - mixed and pumped 75 sxs cement with 500# hulls,
followed with 18 sxs gel.
Topped with 130 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3479	3484		
3335	3368		
3089	3332		

RECEIVED
APR 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE 4-16-04
BY: 2004061429

APR 09 2004

ROBERT R. PRICE OPERATING, INC.

P. O. BOX 470442

TULSA, OK 74147

#2 CHESNEY

5-11-16W

C S/2 SE SE

CONTR RANGER DRILLING CO., INC. CTY ELLIS

GEOLOGICAL FIELD LIEB EXT (1/4 NW)

+	+	+	+
+	+	+	+
+	+	+	+

ELV 1896 KB SPD 11/8/83 CARD ISSUED 5/3/84 IP P 5 BO & 60 BWPD

1891 GL
API 15-051-23.652

SHAW 2847-?

LKC 3089-?

MARM 3335-3366 (EST)

LOG	Tops	Depth/Datum
ANH		1079+ 817
TOP		2812- 916
HEEB		3048-1152
TOR		3070-1174
LANS		3089-1193
BKC		3332-1436
MARM		3335-1439
CONG		3370-1474
SIMP DOL		3467-1571
SIMP SD		3479-1583
ARB		3489-1593
LTD		3544-1646
RTD		3575-1679

8 5/8 " 222 / 225SX; 5 1/2 " 3574 / 225SX
 DST (1) 2828-2860 (TOP) / 60-30-0-0, REC 65" OIL SPTD M, SIP
 1031-989#, NO FP
 DST (2) 2981-3050 (TOP, HEEB) / 60-30-0-0, REC 2683' SW, SIP
 1436-1338#, NO FP
 MICT - CO, PF (ANH) 4 / 1070, SWB DWN, SQZ'D W/275SX, PF
 (MARM) 3335-66 (EST) & (LKC) 3089-? & (SHAW) 2847-?, W / 1
 SPF, 9000G (28% HCL), SWB DWN, SO, POP, P 5 BO & 60
 BWPD. 3/5/84, COMMINGLED

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

INDEXED