

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22616-00-00
Spot: NENENW Sec/Twnshp/Rge: 27-18S-11W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: EISENBERG Well #: 1
County: BARTON Total Vertical Depth: 3350 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

CIBP Size: feet: 3275
CIBP Size: feet: 3330
PROD Size: 4.5 feet: 3345 175 SX CMT
SURF Size: 8.625 feet: 222 150 SX CMT

105⁸⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2004 3:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 265-4651

Proposed Plugging Method: Order 165 sxs 60/40 pozmix - 10% gel and hulls.
Plug while pulling casing.

Plugging Proposal Received By: HERB DEINES

Witness Type: NONE

Date/Time Plugging Completed: 04/13/2004 5:00 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

Sanded well back to 2950' and spotted 4 sxs cement with dump bailer.
Cut casing at 2017' and pulled to 1350'.
Mixed and pumped 65 sxs cement with 200# hulls.
Pulled casing to 600' and pumped 40 sxs cement with 100# hulls.
Pulled casing to 150' and circulated cement with 55 sxs cement.
Pulled casing with cement in cellar.

Perfs:

Top	Bot	Thru	Comments
3345	3350		
3303	3305		
3240	3248		
3065	3076		
3046	3048		
3029	3034		

RECEIVED
APR 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 4-16-04
SER. NO. 200406.1430

APR 14 2004

REF OIL OPERATIONS INC

OWLE

UNNOTICED

REPLACEMENT CARD

HOVSINGTON, KS 67544
CONTR REV LIN DRILLING

#1 EISENBERG

27-18-11W
NE NE NW

SECL JIM MUSGROVE

FIELD AMES

1778 KB ON 12/5/81 CARD ISSUED 5/25/82 P 12 BO & 20 BWP

API 15-009-22,616

LKC - 3046-48

LOG	TOPS	DEPTH	DATUM
NAMU	560	-1216	
#B ANL	685	-1195	
HEES	2887	-1109	
TOR	2905	-1128	
DOUG	2914	-1156	
LANS	3018	-1240	
BKC	3261	-1485	
COOG	3261	-1505	
COOG SD	3382	-1524	
ARS	3334	-1556	
LTD	3346	-1557	
RTD	3350	-1572	
WDLRS TOPS			

8-5/8" 222/150sx, 4 1/2" 3346/178sx

DST (1) 3022-32(LKC)/45-50-45-45, 275/34", GA MAX 4450 CFQPD, REC 50' OOM, 60' WDY C, 120' FROGGY C, 180' CL C, SIF 450-410#, FP INVALID

DST (2) 3052-3125(LKC)/45-50-45-50, 360' GIP, REC 1500' 22' MW, SIF 1380-1350#, FP 50-500/350-360#

DST (3) 5190-5228(LKC)/50-50-30-30, 30' WM, SIF 650-650#, FP 20-50, 30-50#

REF OIL OPERATIONS INC

#1 EISENBERG

27-18-11W
NE NE NW

DST (4) 5251-3315(PENN,CGL)/MISRUN
MISC - CO, (ARS CH), SWB DWN W/SQ, NAT, AC 250g, SWB DWN & REC WTR, SET SP ABOVE ARS, FP (COOG SD) 3302-336, SWB DWN W/GSO, NAT, POP, P 10.64 BOPD & 60% W, 1/15/82, PRCD DECL CFF PMP, FP (LKC) 3046-48, SWB 3 BOPD, NAT, AC 250g, SWB & CLC 15 BOPD, POP, P 30 BOPD, INITIALLY, DECL & STAB AT 12 BO & 20 BWP, 3/22/82