

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20887-00-01
Spot: NESW Sec/Twnshp/Rge: 32-32S-36W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: JORDAN Well #: 1-32
County: STEVENS Total Vertical Depth: 6540 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

CIBP Size: feet: 5925
PROD Size: 5.5 feet: 6538 WITH 375 SX CMT
SURF Size: 8.625 feet: 1765 WITH 770 SX CMT

21255

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/07/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: AS PER KCC INSTRUCTIONS. SET CIBP @ 4180, CAP CIBP W/20' CMT. DISPLACE HOLE W/9 PPG ABANDONMENT MUD TO +-1815', CUT OFF 5-1/2" CSG & POOH @ +- 1715', SET 100' CMT. PLUG FROM 1915'-1715', DISPLACE 8-5/8" CSG W/ABANDONMENT MUD & CAP W/50' SURFACE PIPE.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2004 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 5925'. PUMP 400# HULLS WITH 25 SX CMT. DISPLACE TO BOTTOM WITH 63 BBL MUD. PRESSURE TO 1000 PSIG & SHUT IN. RUN HOLE TO 1770'. PERFORATE 5 1/2". PUMP 375 SX CMT INSIDE 5 1/2" & 5 1/2" X 8 5/8" ANNULUS FROM 1770' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5982	6045		
4201	4205		

RECEIVED


APR 15 2004

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED

DATE

4-15-04

BY

20040618

APR 15 2004