

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-20895-00-00
Spot: SWSW Sec/Twnshp/Rge: 4-35S-20W
660 feet from S Section Line, 560 feet from W Section Line
Lease Name: BOX RANCH A Well #: 1
County: COMANCHE Total Vertical Depth: 5636 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

PROD Size: 5.5 feet: 5636 WITH 200 SX CMT
SURF Size: 8.625 feet: 699 WITH 800 SX CMT

#183¹⁷

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/08/2004 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND BACK TO 5020' WITH 5 SX CMT. 10SX GEL & 50 SX CMT AT 725'. PLUG AT 240' WITH 30 SX CMT. PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2004 11:15 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

SAND TO 5020' WITH 5 SX CMT ON TOP. 1ST PLUG PULL CASING TO 725' & SPOT 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 240' & SPOT 30 SX CMT. 3RD PLUG PULL TO 40' WITH 10 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5070	5074		

RECEIVED
APR 16 2004
KCC WICHITA


Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4010' OF 5 1/2" CASING

Plugged through: CSG

District: 01

RECEIVED
APR 14 2004
KCC Dodge City

Signed



(TECHNICIAN)

INVOICE

DATE 4-16-04
INV. NO. 2004061427

