

6 030749

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,582-00-00

CSWSE, SEC. 30, T. 1 S, R. 29

660 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name BEA WOLF Well # 1

Operator: F & M OIL CO. INC.

County DECATUR 137.35

Name & Address 422 UNION CENTER

Well Total Depth 4226' feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON KELSO CASING License Number 6080

Address OBERLIN KANSAS - CHASE KANSAS

Company to plug at: Hour: PM Day: 22 Month: 5 Year: 19 86

Plugging proposal received from TOM

(company name) KELSO CASING (phone) _____

were: 8 5/8 @ 306 w/ 225 SX. 4 1/2 @ 3941' w/ 250 SX. PERF 3628-3666

PBTD 3715' ORDER SAND & COM. CMT. SHOOT & PULL PIPE

ORDER 200 SX. 65/35 PM. 10% GEL 3% ECONOLITE 4 SX. HULLS.

HALLIBURTON

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:10 PM Day: 22 Month: 5 Year: 19 86

ACTUAL PLUGGING REPORT SAND ON PBTD TO 3570 SPOT 4 SX. COM CAT ON SAND

W/BAKER. SHOT & RECOVERED 1200'

TIE ON TO 4 1/2" MIX & PUMP 3 SX. HULLS 200 SX. CMT. MIX + 1

SX. HULLS. MAX. PSTI 300* CLOSE IN 300* PLUG COMPLETE

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1986
6-16-1986

17-86
6-13-86

Remarks: _____

(If additional description necessary, use BACK of this form.)

INVOICED

DATE JUN 18 1986

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 14159