

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21513-00-00
Spot: SENE SW Sec/Twnshp/Rge: 18-30S-18W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: KANE TRUST Well #: 2-18
County: KIOWA Total Vertical Depth: 5149 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 4.5 feet: 5149 WITH 200 SX CMT
SURF Size: 8.625 feet: 655 WITH 165 SX CMT

816734

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/01/2004 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4800' & 4 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 675' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/01/2004 4:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5118'. SAND TO 4800' WITH 4 SX CMT ON TOP. 1ST PLUG PULL TO 1050' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 675' & SPOT 50 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. 4/5/04: TAGGED PLUG @ 546'. FLUID @ 350'. TOPPED OFF WITH 100 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5057	5061		
5031	5033		
5017	5019		
4863	4865		

RECEIVED
APR 08 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4000' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

[Signature]
(TECHNICIAN) SA

INVOICED
4-8-04
2004061401