

15-039-20339-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

JAN 26 1977
1-24-1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name S & W Drilg. Co. Inc.

Complete Address Box 132, Oberlin Kan.

Lease Name Dowling Well No. 1

Location SW-SW-NW- Sec. 8 Twp. 1 Rge. 28(E) (W) 1

County Decatur Total Depth 3660

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling Co

Address Box 176, Chase Ks. License No. 683

Operation Completed: Hour 12:00 PM Day 20 Month Jan. Year 1977

The above well was plugged as follows:

KB. 2469. Dzk top. 1500' SP. 266' of 8 5/8" c/wc. 160 sx
4 1/2" set @ 3650' w/225 sx. Plug Back. 3630'
Perf. 3542 to 48' Pushed Plug to 3500' w/20' of Sand
+ 3 sx com. cem. Recovered 2292' of 4 1/2" casing.
Pumped down. 8 5/8" SP. 3 sx. Halls, 70 sx cem. 50 Perm
6 7/8 Gel. 15 sx Gel. Release Plug. & 60 " " " "
" " Max. Pres. 300 lbs. Shut in. Pres. 150 lbs.
Halliburton Cementing -

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: J. L. Potholm
Well Plugging Supervisor

DATE 1-24-77
INV. NO. 45147W