

15-039-00534-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API Number April 24, 1957 (of this well) (This must be listed; if no API# was issued, please note drilling completion data.) 6/89

LEASE OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000  
1320' FNL

LEASE (FARM) Warner UNIT WELL NO. 302 WELL LOCATION 2310' FWL COUNTY Decatur

SEC. 11 TWP. 1S RGE 27 (W) Total Depth 3400' PLUG BACK TD 3290'

CHECK ONE:

OIL WELL X GAS WELL      D & A      SWD OR INJ WELL      DOCKET NO.     

SURFACE CASING SIZE 8-5/8" SET AT 256' CEMENTED WITH 225 SACKS

CASING SIZE 5-1/2" SET AT 3370' CEMENTED WITH 200 SACKS

PERFORATED AT 3163-3285' (6 sets perforations)

CONDITION OF WELL: GOOD      POOR      CASING LEAK X JUNK IN HOLE X

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Proposed plugging procedure is attached.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES

IS ACO-1 FILED? NO

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: 4-30-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

NAME J. D. Hininger PHONE # (913) 674-2182  
ADDRESS OXY USA INC., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR Poe Servicing, Inc.\* LICENSE NO.       
ADDRESS Box 115, Oberlin, KS 67749 PHONE # (913) 475-3422

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Raymond Hill  
(Operator or Agent)

\*Anticipated - Service Co.

RECEIVED  
STATE CORPORATION COMMISSION  
04-18-89  
APR 18 1989

DATE: 4-17-89

CONSERVATION DIVISION  
Wichita, Kansas





MEMORANDUM  
OCCIDENTAL OIL AND GAS

Wichita, Kansas  
April 13, 1989

TO: Mr. M. D. Harrison  
FROM: Mr. P. W. Pringle  
SUBJECT: PLUGGING PROCEDURE..... WARNER UNIT #302  
1320' FNL - 2310' FWL  
SECTION 11-T1S-R27W  
DECATUR CO., KS

WELL DATA:

8-5/8" Casing @ 256' w/225 sx  
5-1/2" Casing @ 3370' w/200 sx  
Perforations: 3163-3285'  
PBSD 3290'  
\* 2-3/8" tubing stuck @ approx. 3050'

SHALLOW FORMATION DATA:

Dakota 860'  
Cheyenne 1200'  
Anhydrite 1855'

- 
1. Prior to plugging, obtain approval of project from the KCC office #4, Hays, Kansas (913 - 628-1200).
  2. Back off the 2-3/8" tubing at free point, pull and lay down tubes.
  3. Perforate the well at 1170' and 1845' w/4 SPF.
  4. Run 2" workstring to bottom and spot 65/35 Pozmix w/6% gel plus hulls to surface (approximately 276 sx cement + 600 # hulls).
  5. Tie onto the 8-5/8" casing and pump 100 sx (same) cement down casing annulus.
  6. Let slurry set 48 hrs, check T.O.C. & cap well.

NOTE: Calculations based on 65/35 Pozmix w/6% gel, blended w/  
10.9 gals water/sk cement, slurry volume 1.97 ft<sup>3</sup>/sk.

RECEIVED

9 1989



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
MARGALEE WRIGHT COMMISSIONER  
JUDITH McCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE  
JUL 18 1989  
EXPIRES

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

April 18, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

OXY USA, Inc.  
P. O. Box 26100  
Oklahoma City, OK 73126-0100

Warner Unite #302  
1320' FNL 2310' FWL  
Sec. 11-01S-27W  
Decatur County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*  
Shari Feist Albrecht  
Director

District: #4 2301 E. 13th  
Hays, KS 67601  
(913) 628-1200