

KANSAS CORPORATION COMMISSION RECEIVED
OIL & GAS CONSERVATION DIVISION

Form CP-1
September 2003

This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION APR 15 2004

Please TYPE Form and File ONE Copy

KCC WICHITA

15-007-20926-00-01

API # 15-007-2096-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 6/11/03

Well Operator: WOOLSEY OPERATING COMPANY, LLC KCC License #: 33186⁶⁸

Address: 125 N. MARKET, SUITE 1000 City: WICHITA

State: KANSAS Zip Code: 67202 Contact Phone: (316) 267-4379 X107

Lease: POWELL Well #: 1-36 OWWO Sec. 36 Twp. 33 S. R. 11 East West

S2 - NW - NW Spot Location / QQQQ County: BARBER

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: NONE Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 308' Cemented with: N/A Sacks

Production Casing Size: 4 1/2" Set at: 4750' Cemented with: 185 Sacks

List (ALL) Perforations and Bridgeplug Sets: PF 4612 - 30'

Elevation: 1475 (G.L. / K.B.) T.D.: 4750' PBTD: 4716' Anhydrite Depth: N/A

Condition of Well: Good Poor Casing Leak Junk in Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): SET CIBP @ 4600'. BAIL 2 SX CMT. ON CIBP. CUT & PULL CSG. GIH WITH TUBING & SET 50 SX 60/40 POZMIX / 6% GEL PLUG @ 900'. PULL UP & SET ANOTHER 50SX PLUG @ 330'. PULL TO 40' & CMT TO SURFACE.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: CARL DURR

WOOLSEY OPERATING COMPANY, LLC Phone: (620) 886-5606 X27

Address: 1966 SE RODEO DR. City / State: MEDICINE LODGE, KS

Plugging Contractor: CLARKE CORPORATION KCC License #: 67404 5105^{4/04}

Address: PO BOX 187 MEDICINE LODGE, KS Phone: (620) 886-5665

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4-12-04 Authorized Operator / Agent: _____ (Signature)

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Woolsey Operating Company, LLC
125 N. Market, Suite 1000
Wichita, KS 67202-1775

April 19, 2004

Re: POWELL #1-36 OWWO
API 15-007-20926-00-01
S2NWNW 36-33S-11W, 990 FNL 660 FWL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely,



David P. Williams
Production Supervisor