

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-163-0177400.00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 04-19-1950

Well Operator: H & B Petroleum Corporation KCC License #: 32158
(Owner/Company Name) (Operator's)

Address: P.O. Box 277 City: Ellinwood

State: Kansas Zip Code: 67526 Contact Phone: (620) 564 - 3002

Lease: Darrel Well #: 2 Sec. 34 Twp. 9 S. R. 20 East West

C - NE - NE - NW Spot Location / QQQQ County: Rooks

8/04

RSP/KC

330 ~~4290~~ ~~4950~~ Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990 ~~4258~~ Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Cl. OP 4-21-04
Loc. Per
Orig. State

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____

Surface Casing Size: 8 5/8 Set at: 1759 Cemented with: 750

Production Casing Size: 5 1/2 Set at: 3823 Cemented with: 100

List (ALL) Perforations and Bridgeplug Sets: CIBP 3750 Open Hole 3823 to 3827

Elevation: 2264 (G.L. / K.B.) T.D.: 3827 P.B.T.D.: 3750 Anhydrite Depth: 1752
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):

310 sxs 60/40 pos w/ 10% gel and 500# hulls total. Tubing to 3700'. Spot 100 sxs w/ 200# hulls, 2255'; 100 sxs w/ 200# hulls 800'; 60 sxs w/ 100# hulls. Squeeze from surface. Check braden head.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? **Will send with original

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Al Hammersmith

H & B Petroleum Corporation Phone: (620) 564 - 3002

Address: P.O. Box 277 City / State: Ellinwood, Kansas 67526

Plugging Contractor: Allied Cementing KCC License #: Non required
(Company Name) (Contractor's)

Address: 24 South Lincoln St., Russell, Kansas 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): 04-22-2004

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 04-21-2004 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
APR 21 2004
CONSERVATION DIVISION
WICHITA, KS

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

H & B Petroleum Corp.
520 S. Holland, Suite 307
Wichita, KS 67209

April 21, 2004

Re: DARRELL #2
API 15-163-01774-00-00
NENWNW 34-9S-20W, 330 FNL 990 FWL
ROOKS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely



David P. Williams
Production Supervisor