

15-039-00130-00-00

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1961
7-28-1961
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Decatur

Location: CSE NE Sec. 7 Twp. 1 Rge. _____ (E) _____ (W) 28

Name of Field: _____ Total Depth: 3820

I have this date completed supervision of plugging of:

Lease Name: Kathka Well No. 1

Operator's Full Name: Empire Drg Co

Complete Address: 650 4th Natl Bk Bldg Wichita, Kansas

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 22 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 221' circulated with cement - 5 1/2" 3820' with 100 sax cement -PB 3790'

Perforated 3560'.

Set plugs and sand to 3500', set 5 sax cement with dump bailer, pulled

1676' 5 1/2" to 500', circulated hole with heavy rotary mud from pits,

displaced 20 sax cement through 5 1/2" vat 500', heavy mud to 150', displaced

20 sax cement through 5 1/2" at 150', heavy mud to 35', set bridge and cement

to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 8/9/61

INV. NO. 3521-W