

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-039-20325-00-00  
Spot: SESENE , Sec/Twnshp/Rge: 7-1S-28W  
2310 feet from N Section Line, 330 feet from E Section Line  
Lease/Unit Name: IVAL E KATHKA Well Number: 1  
County: DECATUR Total Vertical Depth: 3840 feet

Operator License No.: 5669  
Op Name: HELBERG, JERRY M DBA HELBERG OI  
Address: PO BOX 32  
MORLAND, KS 67650

Production Casing Size: 4.5 feet: 3806 110 SX CMT  
Surface Casing Size: 8.625 feet: 211 125 SX CMT

*012480*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/16/2003 10:00 AM

Plug Co. License No.: 5669 Plug Co. Name: HELBERG, JERRY M DBA HELBERG OIL COMPANY

Proposal Rcvd. from: JERRY M. HELBERG Company: HELBERG, JERRY M DBA HELBER Phone: (785) 627-5665

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Top down. Squeeze backside.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/16/2003 11:00 AM

KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

Perforations at 3541' - 3542' with three shots. TD 3840'.  
8 5/8" S.P. set at 211' w/125 sxs.  
4 1/2" production casing set at 3806' w/110 sxs.  
Connected to 4 1/2" production casing. Pumped 165 sxs cement with 300# hulls.  
Max. P.S.I. 700#. S.I.P. 300#.  
Connected to 8 5/8" surface casing. Pumped 60 sxs cement with 100# hulls.  
Max. P.S.I. 100#. S.I.P. 100#.

RECEIVED  
JUL 22 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

INVOICED

DATE 7.23.03

INV. NO. 2004060094

JUL 17 2003

