

15-153-20128-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
1129-1971

Operator's Full Name Massey and Moore,

Complete Address Box #592, Cushing, Oklahoma.

Lease Name Kastens Well No. 1

Location CNW-SW Sec. 14 Twp. 1 Rge. (E) (W)32

County Rawlins Total Depth 4265'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated         

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.         

Operation Completed: Hour 12:30 PM Day 21 Month 11 Year 1971

The above well was plugged as follows:

330'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1800'.

Circulated hole with heavy mud. Pulled DP to 2025' and displaced 100 Sx. cement thru  
DP from 2025' to 1700'. Pulled DP to 370' and displaced 25 Sx. cement thru DP from  
370' to 295'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INDEXED  
DATE 12-1-71  
INV. NO. 4743-W

Signed: *W. S. Nichol*  
Well Plugging Supervisor