

15-153-30005-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1963

12-26-1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address: 650 4th National Bank Bldg., Wichita, Kansas.

Lease Name Wicke Well No. 1

Location CNW-SE Sec. 5 Twp. 1 Rge. (E) (W) 32

County Rawlins Total Depth 4150

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractors: Above

Address: License No.

Operation Completed: Hour 7:00PM Day 16 Month 12 Year 1963

The Above well was plugged as follows:

204'--8 5/8" Surface pipe, cement circulated.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx cement
thru DP. Heavy mud to 190', set plug with 1/4 Sk. hulls and displaced 20 Sx.
cement thru DP. Heavy mud to 40', set plug with 1/2 Sk. hulls and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 8343-W 12-26-63

Signed: M. D. Nichols
Well Plugging Supervisor

INV. NO. 8343-W

INVOICED