

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
10 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

API NUMBER 15-065-02167-00-01  
LEASE NAME Bellerive  
WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2310 Ft. from S Section Line  
2970 Ft. from E Section Line

EASE OPERATOR Raney Oil Company, LLC.  
ADDRESS 3415 Tam O'Shanter Lawrence, Kansas 66047

SEC. 9 TWP. 10S RGE. 25W (E) or (W)  
COUNTY Graham

PHONE# (785) 749-0672 OPERATORS LICENSE NO. 32705

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 4-2-04

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-6-04

The plugging proposal was approved on 6-9-03 (date)

by Roger Moses (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4060'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>			<u>215</u>	<u>8-5/8"</u>	<u>215'</u>	<u>None</u>
<u>Prod</u>			<u>467</u>	<u>4-1/2"</u>	<u>4167'</u>	<u>1575'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Plugged off bottom with sand to 3740' and 4 sacks cement. Cut 4-1/2" casing loose @1575'. pulled up to 1340', pumped 70 sacks cement and 200# hulls, pulled up to 500' and pumped 30 sacks cement with 100# hulls, pulled up to 200' and circulated 50 sacks cement. Topped off with 20 sacks cement, 60/40 pos. 10% gel. Plugging Complete

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Raney Oil Company, LLC.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 20th day of April, 2004

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
APR 22 2004  
KCC WICHITA