

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

SE NW SW
15.163.01467-00-01
API NUMBER ~~45-8/62~~
LEASE NAME Hrabe A

RECEIVED
APR 16 2004

KCC WICHITA

WELL NUMBER #2

NOTICE: Fill out completely 1650 Ft. from S Section Line
and return to Cons. Div. 4290 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 1 TWP9S RGE. 17W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Rooks
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 8/62
Character of Well Oil, Gas, D&A, SWD, Input, Water Supply Well Plugging commenced 3/09/04
Plugging Completed 3/09/04

The plugging proposal was approved on 3/09/04 3/15/04 (date)
by Rich Williams w/KCC in Hays, KS (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? _____
Producing Formation LKC Depth to Top 3142 Bottom 3353 TD 3439 Show depth and thickness of
all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	166	8 5/8	166	0
		Production	3438 <u>3439</u>	4 1/2	3438 <u>3439</u>	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ____ feet to ____ feet each set.

Plugged well as follows:

RIH w/2 3/8" mule shoe & 2 3/8" tbg to 892'. RU Swift Services. Tied onto 2 3/8" tb. Pumped 40 sacks SMD to circ cmt to surface. TOH w/tbg. Tied onto 4 1/2" csg. Pumped 35 sacks SMD, 65 sacks SMD w/200# hulls. Max pressure 800#, ISIP 650#. Tied onto 8 5/8". Pumped 18 sacks SMD, 500# max pressure, 300#ISIP. Plugged @11:00 am. Witnessed by Rich Williams w/KCC.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606
Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tom W. Nichols
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 15th day of April, 2004

Notary Public – Kristin Grady

My Commission Expires: 2/06/08

Form CP-4

Revised 05-88



TICKET NO. 6378

JOB TYPE PTA

[illegible]

~~KCC WICHITA~~