

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-159-02376-00-00  
API NUMBER Comp. 5-14-48

LEASE NAME Wendell

WELL NUMBER 1

990 Ft. from X<sup>N</sup> Section Line

2310 Ft. from X<sup>W</sup> Section Line

SEC. 18 TWP. 19 RGE. 10W (E) or (W)

COUNTY Rice

Date Well Completed 5-14-1948

Plugging Commenced 4-7-04

Plugging Completed 4-8-04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

EASE OPERATOR Mike Kelso Oil, Inc.

ADDRESS P.O. Box 467 Chase, Kansas 67524

PHONE(S) (620) 938-2943 OPERATORS LICENSE NO. 31528

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-31-04 (date)

by Virgil Clothier (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3345'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>			<u>250</u>	<u>8-5/8"</u>	<u>250'</u>	<u>None</u>
			<u>3327</u>	<u>5-1/2"</u>	<u>3327'</u>	<u>1540'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3050' and 5 sacks cement. Cut 5-1/2" casing loose @1540 ft. Pulled casing up to 1250', pumped 35 sacks cement, pulled up to 900', pumped 35 sacks cement, pulled up to 300' and circulated 110 sacks cement to surface, 60/40 pos. 4% gel. Pull rest of casing. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Mike Kelso Oil, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED


APR 22 2004

KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 20th day of April, 20 04

[Signature]  
Notary Public

My Commission Expires:



Form CP  
Revised 05-