

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
90 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-20,066-00-01

LEASE NAME Pallister

WELL NUMBER #3 SWD

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 3 TWP. 21 RGE. 7W (E) or (W)

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 4-12-04

Plugging Completed 4-13-04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Rama Operating Company, Inc.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE# (620) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>			<u>209</u>	<u>9"</u>	<u>209'</u>	<u>None</u>
<u>Prod.</u>			<u>3774</u>	<u>7"</u>	<u>3774'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3720' and 7 sacks cement. Perforated 7" casing @1000 ft, 550 ft. and 260 ft. Ran 2-3/8" tubing to 1024', pumped 50 sacks cement, pulled up to 576 ft., pumped 50 sacks cement, pulled up to 288 ft., pumped 120 sacks cement and circulated up 7" and 9" surface. Layed tubing down and topped off with 10 sacks cement, 60/40 pos, 4% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

do hereby certify that the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 20th day of April, 2004

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_



Form B  
Revised 05-

RECEIVED

APR 22 2004

KCC WICHITA