

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-20112-00-00

LEASE NAME Wilhaus

WELL NUMBER 2

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 35 TWP. 20 RGE. 7W (E) or (W)

COUNTY Rice

Date Well Completed 4-30-1968

Plugging Commenced 4-13-04

Plugging Completed 4-14-04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rama Operating Company, Inc.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE# (620) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-5-2003 (date)

Mike Wilson (KCC District Agent's Name).

ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3377' 357'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Sand</u>			<u>213</u>	<u>8-5/8"</u>	<u>213'</u>	<u>None</u>
<u>Prod</u>			<u>3370</u>	<u>5-1/2"</u>	<u>3370'</u>	<u>2320'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3320' and 5 sacks cement. Cut 5-1/2" casing loose @2320'. Pulled casing up to 1093', pumped 35 sacks cement, pulled up to 600', pumped 35 sacks cement, pulled up to 265' and circulated 110 sacks cement to surface. 60/40 pos. 4% gel. Layed down rest of casing. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Company, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED

SUBSCRIBED AND SWORN TO before me this 20th day of April, 2004

APR 22 2004

Jane Herberg
Notary Public

KCC WICHITA

My Commission Expires:

