

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22360-00-00
Spot: NWNW Sec/Twnshp/Rge: 17-32S-35W
1200 feet from N Section Line, 430 feet from W Section Line
Lease Name: HJV KEATING A Well #: 1
County: STEVENS Total Vertical Depth: 6450 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PARKWA
HOUSTON, TX 77210

CIBP Size: feet: 3110 WITH 20 SX CMT
CIBP Size: feet: 3210 WITH 20 SX CMT
PROD Size: 5.5 feet: 3338 WITH 255 SX CMT
SURF Size: 8.625 feet: 1765 WITH 560 SX CMT

H 209 w3

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/20/2004 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 1780' IWHT 50 SX CMT. PLUG AT 600' WITH 30 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 04/21/2004 10:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 3090'. 1ST PLUG PUMP 200# HULLS & 25 SX CMT. 2ND PLUG PUMP 50 SX CMT FROM 1618-1468'. 3RD PLUG PUMP 30 SX CMT FROM 600-500'. 3RD PLUG PUMP 10 SX CMT FROM 40-0'.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3247 | 3280 | | |
| 3230 | 3240 | | |
| 3119 | 3139 | | |

RECEIVED
APR 23 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1618' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
APR 21 2004
KCC Dodge City

Signed Steve Almont
(TECHNICIAN)

INVOICED
DATE 4-23-04
INV. NO 2004061452