

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-20575-00-00  
Spot: NESENW Sec/Twnshp/Rge: 24-31S-36W  
1775 feet from N Section Line, 2540 feet from W Section Line  
Lease Name: WILLIAM MAST Well #: B-2  
County: STEVENS Total Vertical Depth: 3090 feet

Operator License No.: 5208  
Op Name: EXXONMOBIL OIL CORP  
Address: 14950 HEATHROW FORREST PARKWA  
HOUSTON, TX 77210

PROD Size: 5.5 feet: 3090 650 SX CMT  
SURF Size: 8.625 feet: 623 300 SX CMT

100<sup>43</sup>

Well Type: GAS UIC Docket No: Date/Time to Plug: 04/13/2004 1:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 25 SX CMT & 400# HULLS. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/15/2004 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3060'. CASING LEAK @ 2820'. PUMP 400# HULLS & 25 SX CMT THROUGH 2 3/8" TUBING TO PLUG PERFS. DISPLACE WITH 9 BBL MUD. TUBING ON VACUUM. PULL OUT OF HOLE WITH 20 JOINTS 2 3/8" TUBING & CIRCULATE HOLE WITH MUD. HOLE CIRCULATED. PULL OUT OF HOLE WITH 2 3/8" TUBING & LAY DOWN. 04/14/04: PULL STRETCH ON 5 1/2". NO STRETCH. FLUID LEVEL INSIDE 5 1/2" @ 1380'. TOC @ 2840'. DUMP 12 SX CMT ON TOP OF FLUID @ 1380'. SDON. 04/15/04: TAG CMT AT 1215'. FLUID AT 1150'. PUMP 12 BBL MUD TO 650'. PUMP 70 SX CMT DOWN 5 1/2". FILL TO SURFACE. PUMP 5 SX CMT ON BACKSIDE, FILL TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2924	2963		
2897	2911		

RECEIVED  
APR 23 2004  
KCC WICHITA

Remarks: USED COMMON CEMENY BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01

RECEIVED  
APR 20 2004  
KCC Dodge City

Signed

Jim Holland PORT #  
(TECHNICIAN)

INVOICED

DATE 4-23-04  
INV. NO. 2004061452

Form CPMS