

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21033-00-01
Spot: SESESE Sec/Twnshp/Rge: 11-32S-35W
600 feet from S Section Line, 600 feet from E Section Line
Lease Name: WULFEMEYER 1-A UNIT Well #: 3
County: STEVENS Total Vertical Depth: 6280 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PARKWA
HOUSTON, TX 77210

CIBP Size: feet: 3001
CIBP Size: feet: 5900
PROD Size: 5.5 feet: 6280 605 SX CMT
SURF Size: 8.625 feet: 1724 779 SX CMT

204' 10"

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/06/2004 9:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 500' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/06/2004 5:00 PM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:

Perfs:

PBTD 3001'. PUMPED DOWN 5 1/2" 500# HULLS & 25 SX CMT. DISPLACED WITH MUD. PRESSURED UP CASING TO 500#. 1ST PLUG PULLED UP TO 1750'. CIRCULATED HOLE WITH MUD & PUMPED 50 SX CMT. 2ND PLUG PULLED TO 500' & PUMPED 30 SX CMT. 3RD PLUG PULLED TO 40' & PUMPED 10 SX CMT.

Top	Bot	Thru	Comments
2625	2735		

RECEIVED
APR 23 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2129' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
APR 12 2004
KCC Dodge City

Signed Kevin D. Strube (TECHNICIAN)

INVOICED
DATE 4-23-04
INV. NO. 200406452

Form 682/3