

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-30077-00-01
Spot: NWSE Sec/Twnshp/Rge: 18-33S-41W
2080 feet from S Section Line, 1980 feet from E Section Line
Lease Name: WHITE Well #: 1-18
County: MORTON Total Vertical Depth: 5080 feet

Operator License No.: 32390
Op Name: HIGH PLAINS PRODUCTION, LLC
Address: 1490 COUNTY RD. 1215 PO BOX 228
SAVOY, TX 75479

CIBP Size: feet: 2800 WITH 2 SX CMT
CIBP Size: feet: 3224
PROD Size: 5.5 feet: 3438 WITH 250 SX CMT
SURF Size: 8.625 feet: 1485 UNKNOWN

6/104 45

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/15/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RON OSTERBUHR Company: HIGH PLAINS PRODUCTION Phone: (620) 275-7888

Proposed Plugging Method: SET A CIBP @ 2800', 2 SX CMT ON TOP OF PLUG, PERFORATE AT 1500', AND CIRCULATE 60/40 POZ MIX CMT BACK TO THE SURFACES TO FILL THE 5.500" CASING AND THE ANNULUS BETWEEN THE SURFACE CASING A PRODUCTION CASING. CUT OFF THE CASING 3' BELOW GROUND LEVEL AND WILD A PLATE ON TOP. AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2004 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 2800' WITH 2 SX CMT ON TOP. LOAD HOLE, TEST TO 300 PSIG. PERFORATE AT 1500'. PUMP 350 SX CMT FROM 1500' TO SURFACE INSIDE 5 1/2" & 5 1/2" X 8 5/8" ANNULUS. GOOD CIRCULATION.

Perfs:

Top	Bot	Thru	Comments
3233	3239		
3199	3203		
3175	3179		
2964	2970		
2932	2938		
2924	2928		
2910	2913		
2900	2904		
2891	2896		

RECEIVED
APR 23 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

RECEIVED
APR 20 2004
KCC Dodge City

Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED

DATE 4-23-04

INV. NO. 2004061454

Form *[Signature]*