

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21142-00-00
Spot: SWSE Sec/Twnshp/Rge: 4-33S-22W
560 feet from S Section Line, 2030 feet from E Section Line
Lease Name: NUNEMACHER Well #: 1-4
County: CLARK Total Vertical Depth: 5450 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

PROD Size: 4.5 feet: 5441 WITH 310 SX CMT
SURF Size: 8.625 feet: 839 WITH 530 SX CMT

\$177¹³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2004 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 5200' WITH 4 SX CMT. PLUG AT 875' WITH 70 SX CMT. PLUG AT 250' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT. 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2004 11:10 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5290'. SAND TO 5200' WITH 4 SX CMT. 1ST PLUG PULL CASING TO 860' & SPOT 10 SX GEL & 70 SX CMT. 2ND PLUG PULL CASING TO 250' & SPOT 30 SX CMT. 3RD PLUG PULL CASING TO 40' & SPOT 10 SX CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5298	5304		
5262	5270		

RECEIVED
APR 23 2004
KCC WICHITA


Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4200' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
APR 20 2004
KCC Dodge City

Signed


(TECHNICIAN)
INVOICED
DATE 4-23-04
2004061458

Form 