

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-33297-00-00
Spot: NWNENW Sec/Twnshp/Rge: 36-24S-15W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: SATTERLEE Well #: 1
County: STAFFORD Total Vertical Depth: 4385 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

L1 Size: 4.5 feet: 2390 WITH 100 SX CMT
PROD Size: 5.5 feet: 4370 WITH 75 SX CMT
SURF Size: 8.625 feet: 282 WITH 290 SX CMT

142⁵¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2004 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PUMP 500# HULLS & 50 SX CMT TO BOTTOM. PERFORATE AT 960'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2004 3:42 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 960'. SQUEEZED 1597-1800' WITH 275 SX CMT. PUMPED 400# HULLS & 50 SX 60/40 POZMIX 6% GEL 3% CC. DISPLACED TO 4100'. MAXIMUM PRESSURE 1000 PSIG. SHUT IN PRESSURE 800 PSIG. PERFORATED 5 1/2" & 4 1/2" @ 960'. PUMPED 425 SX CMT DOWN 4 1/2" CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS. CMT TO SURFACE IN 5 1/2" X 4 1/2" ANNULUS VISUALLY CHECKED.

Perfs:


Top	Bot	Thru	Comments
4370	4385	OH	

RECEIVED
APR 19 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED NO CASING RECOVERED

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 4-20-04
NO. NO. 2004061438

Form 0128