

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15123-00-00
Spot: NENWNW Sec/Twnshp/Rge: 33-16S-11W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HARZMAN V O Well #: 6
County: BARTON Total Vertical Depth: 3345 feet

Operator License No.: 5147
Op Name: BEREDCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

L1 Size: 2.875 feet: 3330 w/125 sxs cmt
PROD Size: 4.5 feet: 3339
SURF Size: 8.625 feet: 358

108 71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2004 2:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DENNIS KIRMER Company: BEREDCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well has an open hole.
Perf Tech perfed at 465' - 780' - 1465'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2004 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Ran in hole with tubing to 2485' - pumped 85 sxs cement with 300# hulls mixed in.
Pulled tubing to 1500' - pumped 60 sxs cement with 200# hulls to circulate cement to surface.
Cement also circulated out of backside - shut in backside.
Pulled tubing and rigged to 8 5/8" casing with a swedge - pumped 20 sxs 60/40 pozmix.
Max. P.S.I. 400#. S.I.P. 200#.


Remarks: ALLIED CEMENTING COMPANY-TICKET #7015.

Plugged through: TBG

RECEIVED
APR 19 2004
KCC WICHITA

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 4.20.04

WV. NO. 2004061432

Form CP-2/3

APR 15 2004

SHELL OIL CO INC

#6

V O HARZMAN

33-16-11W
NE NW NW

Contr.

BARTON

County

E. 1903

Comm. 5-30-42

Comp.

6-20-42

IP

3000 BOPD

Tops	Depth	Datum
ANHY	753	
TOP	2700	
LANS	3063	
ARB	3337	
TD	3345	

Casing

8" 358

4" 3338 or 3339

A/1000

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

312
312
312