

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23672-00-00
Spot: NWSENW Sec/Twnshp/Rge: 33-16S-11W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HARZMAN Well #: 7
County: BARTON Total Vertical Depth: 3500 feet

Operator License No.: 5147
Op Name: BEREDCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

PROD Size: 7 feet: 3499 w/255 sxs cmi
SURF Size: 10.75 feet: 784 w/400 sxs cmt

\$ 113.⁷⁵

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/14/2004 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DENNIS KIRMER Company: BEREDCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 650 sxs 60/40 pozmix - 10% gel - 1000# hulls.
Bridge plugs at 3395' - 3330'.
Perf Tech perfed at 485' - 800' - 1485'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2004 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2575' - pumped 100 sxs 60/40 pozmix with 700# hulls mixed in.
Pulled tubing to 1495' - pumped 150 sxs cement with 200# hulls mixed in.
Pulled tubing to 800' - pumped 110 sxs cement with 100# hulls to circulate cement into pit.
Pulled tubing - tied onto 10 3/4" casing with a swedge and pumped 165 sxs cement to circulate cement out of backside.
Shut in backside and pumped 10 sxs cement.
Max. P.S.I. 600#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
2919	3372		

RECEIVED
APR 19 2004

Remarks: ALLIED CEMENTING COMPANY-TICKET #17014.

KCC WICHITA

Plugged through: TBG

District: 04

Signed

[Signature]

(TECHNICIAN)

INVOICED

DATE

4-20-04

W.V. NO.

2004061432

Form CP-2/3

APR 15 2004

SAMSON RESOURCES COMPANY
2 W. SECOND ST.

#7 HARZMAN

33-16-11W
NW SE NW

TULSA, OK 74103

WHITE & ELLIS DRILLING CTY BARTON

JAMES MUSGROVE FIELD KRAFT-PRUSA

1932 RECD 9/12/84 CARD ISSUED 12/27/84 IP P 12 RO & 147 BWPD
1937 RI SHAW 2919-2997
LKC 3090-3272 11A

1	2	3	4	5	6	7	8	9	10	11	12

Log	Depth Down
POP	2683-751
BIT	2974-1042
FEI	2989-1057
DOUG	3003-1071
TRIM	3070-1133
LAHS	3083-1151
COING	3360-1428
ARIB	3377-1445
REAG	3401-1469
GR WSH	3451-1519
GRAN	3494-1562
LTD	3498-1566
RTD	3500-1568

API 15-009-23,672

10 3/4" 784 / 400SX, 7" 3499 / 255SX
NO DST'S OR CORES
MICI - CO, PF (TOR) 2919-24 W/2 SPF, AC 500G (15%), SWB
DOWN, SO, PF (TOR) 2993-97 W/2 SPF, AC 500G (15%), SWB
DOWN, SO, PF (LKC) 3090-93 & 3118-22 W/2 SPF, AC 500G
(15%), SWB DOWN, SO, PF (LKC) 3169-76, SWB DOWN, SO, NAT,
PF (LKC) 3264-72, AC 2000G (15%), SWB DOWN, SO, SET 2 7/8"
TBG AT 3324', POP, P 12 RO & 147 BWPD - COMMINGLED

NOTE: CORRECTION 10/25/84 - ORIGINALLY FIRST REPORTED AS
1080'FNL&1360'TEL, NE/4, 33-17-11W

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

WICHITA
KANSAS
11/10/84