

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20341-00-00
Spot: NENW Sec/Twnshp/Rge: 29-19S-20W
766 feet from N Section Line, 1874 feet from W Section Line
Lease Name: WELLS Well #: 29-3
County: RUSH Total Vertical Depth: 4445 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

PROD Size: 4.5 feet: 4447 WITH 300 SX CMT
SURF Size: 9.625 feet: 357 WITH 150 SX CMT

114 46

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2004 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4300' & 4 SX CMT. PERFORATE AT 600'. PUMP 80 SX CMT OVER CAPACITY OF 4 1/2". PRESSURE 8 5/8" X 4 1/2" ANNULUS TO 500# WITH CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2004 1:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4402'. ANHYDRITE 1460-1484'. SQUEEZED AT 1633-64' WITH 150 SX CMT. SANDED TO 4300' & 4 SX CMT WITH BAILER. PERFORATED AT 600'. PUMPED 150 SX CMT DOWN 4 1/2" CASING. MAXIMUM PRESSURE 900 PSIG. SHUT IN PRESSURE 350 PSIG. PUMPED 50 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 500 PSIG.

Perfs:


Top	Bot	Thru	Comments
4364	4382		

RECEIVED
APR 19 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE

4-20-04

IN. NO.

2004061438

Form *CS-2/B*