

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21962-00-00  
Spot: SENE SW Sec/Twnshp/Rge: 9-14S-13W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: PARKHURST A Well #: 1  
County: RUSSELL Total Vertical Depth: 2490 feet

Operator License No.: 4952  
Op Name: SCHLOBOHM, STARR F.  
Address: 47 MICHAWANIC ROAD #3D  
SANBORNVILLE, NH 03872

PROD Size: 4.5 feet: 2474 60 SX CMT  
SURF Size: 7 feet: 511 175 SX CMT

\$/ 80<sup>93</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/23/2004 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOHN L DRISCOLL Company: SCHLOBOHM, STARR F. Phone: (785) 483-9580

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/23/2004 10:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 2319' and dumped 5 sxs cement.  
Cut off casing at 1720'.  
Pulled to 1400' - pumped 80 sxs 60/40 pozmix - 10% gel cement with 300# hulls.  
Pulled to 840' - pumped 25 sxs cement with 100# hulls.  
Pulled to 520' - pumped 25 sxs cement with 100# hulls.  
Pulled to 200' and circulated with 30 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2403	2413		
2380	2388		

RECEIVED  
APR 19 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100-

Signed

Case Morris  
TECHNICIAN)

INVOICED  
DATE 4-20-04  
BILL NO. 2004061434

Form CP-2/3

APR 14 2004

A. SCOTT RITCHIE  
125 N. MARKET, #950  
WICHITA, KS 67202

#1 "A" PARKHURST

9-14-13W  
SE NE SW


CONTR GLACIER DRILLING COMPANY CTY RUSSELL

GEOL \_\_\_\_\_ FIELD HALL-GURNEY

ELV 1857 KB SPD 8/11/82 CARD ISSUED 1/20/83 IP P 2.5 BO & 146 BWPD

API 15-167-21,962

WAB (TARK) 2380-2413 OA



SMP	Tops	Depth	Datum
ANH	808	1049	
B ANH	845	1012	
IND CV	2326	469	
GR HAV	2371	514	
1ST TARK SD	2385	528	
2ND TARK SD	2404	547	
TARK LS	2441	584	
WILLARD SH	2460	603	
RTD	2490	633	
NO LOG			

7" 511.7 175SX; 4 1/2 " 2474-60SX

NO DSTS

MICT - CO, PF (TARK) 2380-2388, 2403-2413, W / 2 SPF, AC  
500G. FRAC W. 500 BBLs GEL WTR & 150 SX SD, FL DWN 900'  
SWB AVG 15 BFPH. ALL WTR / 4 HRS, FL 1200' IN HOLE, SWB  
DWN. SWB AVG 15 BFPH. ALL WTR / 8 HRS, ONFU 1200' FL, NO  
OIL. BAILED SD FROM 2410-2431, R&T, POP, P 2 1/2 BO & 146  
BWPD

NOTE: ORIGINALLY FIRST REPORTED AS #2 PARKHURST

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS