

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-21152-00-00  
Spot: E2E2SW Sec/Twnshp/Rge: 4-33S-22W  
1320 feet from S Section Line, 3120 feet from E Section Line  
Lease Name: NUNEMACHER Well #: 3-4  
County: CLARK Total Vertical Depth: 5398 feet

Operator License No.: 31925  
Op Name: QUALITY WELL SERVICE, INC.  
Address: 401 WEST MAIN  
LYONS, KS 67554

PROD Size: 4.5 feet: 5392 WITH 150 SX CMT  
SURF Size: 8.625 feet: 667 WITH 350 SX CMT

*# 175 44*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/13/2004 10:45 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: PLUG AT 950' WITH 50 SX CMT. PLUG AT 670' WITH 50 SX CMT. PLUG AT 250' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT. 10 SX GEL ON SIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/13/2004 12:40 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5330'. SAND TO 5200' WITH 4 SX CMT. 1ST PLUG PULL CASING TO 960' & SPOT 10 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 670' & SPOT 50 SX CMT. 3RD PLUG PULL TO 250' & SPOT 30 SX CMT. 4TH PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
5266	5274		

RECEIVED  
APR 19 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4400' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*[Signature]*

(TECHNICIAN)

INVOICED

DATE 4-20-04

WEL. NO. 2004061435

Form CP 2/3  
*[Signature]*