

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21149-00-00
Spot: NWSE Sec/Twnshp/Rge: 4-33S-22W
1980 feet from S Section Line, 2030 feet from E Section Line
Lease Name: NUNEMACHER Well #: 2-4
County: CLARK Total Vertical Depth: 5420 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

PROD Size: 4.5 feet: 5420 WITH 205 SX CMT
SURF Size: 8.625 feet: 621 WITH 245 SX CMT

176¹⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/15/2004 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 5200' WITH 4 SX CMT. PLUG AT 950' WITH 10 SX GEL & 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 350' WITH 30 SX CMT. PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2004 1:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SAND TO 5100' WITH 4 SX CMT. 1ST PLUG AT 950' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 30 SX CMT. 4TH
PLUG AT 0-40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5246	5251		

RECEIVED
APR 19 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 4400' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durrant

(TECHNICIAN)

INVOICED
DATE 4.20.04
VOL. NO. 2004061435