

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21000-00-00  
Spot: S2NE Sec/Twnshp/Rge: 14-35S-26W  
3300 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: LOYD Well #: 1-14  
County: MEADE Total Vertical Depth: 6375 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

CIBP Size: feet: 5320  
CIBP Size: feet: 6210  
PROD Size: 4.5 feet: 6374 WITH 400 SX CMT  
SURF Size: 8.625 feet: 1594 WITH 690 SX CMT

#207.19

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/14/2004 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DENNIS Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 500# HULLS & 40 SX CMT ON BOTTOM. MUD SPACER TO 1600'. CMT TO SURFACE INSIDE 4 1/2".  
CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/14/2004 12:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5320'. PUMPED 500# HULLS & 40 SX CMT. PUMP 8 SX GEL TO 1600'. PUMP 60 SX CMT FROM 1600' TO 0'. PUMP 11 SX CMT DOWN BACKSIDE. SHUT IN PRESSURE 100#. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE ON 4 1/2" 1000#.

Perfs:


Top	Bot	Thru	Comments
6254	6264		
5362	5368		
2956	2970		

RECEIVED  
APR 19 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*[Signature]*

INVOICED (TECHNICIAN)  
DATE 4.20.04  
INV. NO. 2004061433

Form SP-2  
*[Signature]*