

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-039-20161-00-00

API NUMBER June 1970

LEASE NAME DAFFER

WELL NUMBER #1

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 5 TWP. 15 RGE. 26 (X) or (W)

COUNTY Decatur

Date Well Completed June 1970

Plugging Commenced 4/15/88

Plugging Completed 11/10/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PLATTE VALLEY OIL CO., INC.

ADDRESS 253 Hillcrest Center Bldg.

Ralston, Ne. 68127

PHONE# (402) 331-4927 OPERATORS LICENSE NO. 7267

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6, Hays Kansas

Is ACO-1 filed? Yes If not, is well log attached? Sent with CP-1

Producing Formation Lansing Depth to Top 3356 Bottom 3495 T.D. 3627

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing	Oil	Surface	288	8 5/8	288	None
		"	3550	4 1/2	3550	815

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dump sand 50' above top perforations-spotted 4 sks common cement with bailer-shot pipe 2000', 1300' and 815'-pulled 815' casing. Halliburton pumped total of 200 sks cement down tubing until cement came to surface on backside-balance of cement down surface pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PLATTE VALLEY OIL CO., INC. License No. 2024

Address 253 Hillcrest Center Bldg., Ralston, Ne. 68127

STATE OF Nebraska COUNTY OF Douglas, ss.

John Loughran

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Loughran
(Address) 253 Hillcrest Center Bldg. Ralston, Ne. 68127

DEPOSED AND SWORN TO before me this 27 day of January, 1989

Bonita G. Boyesen
Notary Public

CONSERVATION DIVISION
Wichita, Kansas
Commission Expires: 11/30/89

RECEIVED
STATE CORPORATION COMMISSION
1-30-89
JAN 30 1989

BONITA G. BOYSEN
NOTARY PUBLIC, STATE OF NEBRASKA
MY COMMISSION EXPIRES

Form CP-4
Revised 08-84