


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Rawlins County, Sec. 5 Twp. 1 Rge. 32 ~~(E)~~ XXXXXX (W)  
Location as "NE/CNWKSW" or footage from lines NW SE  
Lease Owner Empire Drilling Company  
Lease Name Wicke Well No. 1  
Office Address 650 Fourth Natl. Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 16 19 63  
Application for plugging filed December 16 19 63  
Application for plugging approved December 16 19 63  
Plugging commenced December 16 19 63  
Plugging completed December 16 19 63  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Morland, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4150 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface - Shale & Shells	0	224'	8 5/8"	204'	-0-
	Sand & Clay					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set plug at 600' with 20 sacks cement.  
Set plug at 190' with 20 sacks cement.  
Set plug at 40' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 24 1963

12-24-1963  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Empire Drilling Company  
Address 650 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Dan J. Kornfeld

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld  
650 4th Natl. Bank Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 19 63

My commission expires October 21, 1966.

Lucille H. Harr  
Lucille H. Harr  
Notary Public.

LOG

15-153-30005-00-00

9

COMPANY: Empire Drilling Company  
 CONTRACTOR: Empire Drilling Company  
 FARM: Wicke #1  
 LOCATION: NW SE Section 5-1-32, Rawlins County, Kansas  
 COMMENCED: December 5, 1963 ELEVATION: 2930 KB  
 COMPLETED: December 16, 1963 POTENTIAL: D & A

\*\*\*\*\*

0	to	75	Surface - Shale & Shells
75	to	180	Sand & Clay
180	to	224	Blue Shale
224	to	700	Shale
700	to	1975	Shale - Sand
1975	to	2175	Shale - Gypsum
2175	to	2256	Shale
2256	to	2390	Shale & Sand
2390	to	2520	Shale - Shells
2520	to	2531	Gypsum
2531	to	2744	Redbed
2744	to	2781	Anhydrite
2781	to	2870	Shale & Lime
2870	to	3012	Shale & Shells
3012	to	3755	Lime & Shale
3755	to	3788	Lime
3788	to	3795	Lime & Chert
3795	to	3830	Lime & Shale
3830	to	3915	Lime
3915	to	3960	Lansing Kansas City & Shale
3960	to	3995	Lime
3995	to	4025	Lime - Shale
4025	to	4080	Lime
4080	to	4115	Lime & Shale
4115	to	4150	Lime
4150			Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 24 1963  
 12-24-1963  
 CONSERVATION DIVISION  
 Wichita, Kansas

SET: 204' of 8 5/8" with 125 sacks cement.

SCHLUMBERGER ELECTRIC LOG TOPS:

Topeka	3706	-776
Oread	3810	-880
Douglas Sandstone	3846	-916
Lansing	3866	-936
Base Kansas City	4137	-1207
Log Total Depth	4149	

\*\*\*\*\*

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Wicke #1, NW SE Section 5-1-32, Rawlins County, Kansas, as reflected by the files of Empire Drilling Company.

*Dan J. Kornfeld*  
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 19th day of December, 1963.

*Lucille H. Harr*  
 Lucille H. Harr, Notary Public

My commission expires October 21, 1966.