


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas



Locate well correctly on above Section Plat

Rawlins County. Sec. 15 Twp. 18 Rge. 32W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Maher Well No. 1
Office Address 780 Fourth National Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 2, 1961
Application for plugging filed January 2, 1961
Application for plugging approved January 2, 1961
Plugging commenced January 2, 1961
Plugging completed January 2, 1961
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4210 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	Not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set first plug at 550 feet with 20 sacks of cement; Set second plug at 240 feet with 20 sacks of cement; Set top plug at 40 feet with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc. 2-6-1961
Address 780 Fourth National Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. L. Bacon (employee of ~~XXXXXX~~ or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.
(Signature) By: R. L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 61
My commission expires October 12, 1964
Cecilia C. Klug
Cecilia C. Klug Notary Public.



de

15-193-30010-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita, Kansas

Maher No. 1
C SW NE Sec. 15-1S-32W
Rawlins County, Kansas

Total Depth: 4210'

Elevation: 2985 K.B.
Production: Dry

Commenced: 12-19-60 Completed: 1-2-61

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 250 with 125 sacks of cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	(Sample)
Shale & Shells	250'	Anhydrite	2775 (+ 210)
Shale & Sand	1800'	Topeka	3785 (- 800)
Shale, Iron Pyrite	2490'	Oread	3881 (- 896)
Shale, Iron, Shells	2675'	Lansing	3932 (- 947)
Shale & Shells	2765'	B/Kansas City	4206 (-1221)
Anhydrite	2815'	Total Depth	4210 (-1225)
Shells & Shale	2870'		
Shale	3340'		
Shale & Lime	4210'		
Rotary Total Depth	4210'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By *Raymond L. Bacon*
Raymond L. Bacon

Subscribed and sworn to before me this 9th day of January, 1961.

My Commission Expires:

October 12, 1964

RECEIVED
STATE CORPORATION COMMISSION
2-6-1961
FEB 6 1961

Cecilia C. Klug
Cecilia C. Klug, Notary Public

CONSERVATION DIVISION
Wichita, Kansas