



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 31 1967
05-31-1967
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-153-20010-00-00

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Duane Born of Paine Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated.

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Sattler Well No. 1

Location: CNW-NE Sec. 18 Twp. 1 Rge. (E) (W) 31

County Rawlins Total Depth 4107 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

288' -- 7" OD Surface pipe, cement circulated with 150 Sx.

Circulate hole with heavy mud, set plug @ 660' and 15 Sx. cement.

" " 300' with $\frac{1}{2}$ sk. hulls & 15 Sx. cement.
" " 40' with $\frac{1}{2}$ sk. hulls & 10 Sx. cement.

Very truly yours,

Conservation Division Agent