

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-051-05392-00-00

API NUMBER 15-711152  
LEASE NAME Gus Riedel

RECEIVED

TYPE OF WELL APR 07 2004

WELL NUMBER #11

KCC WICHITA

NOTICE: Fill out **completely** and return to Cons. Div. office within 30 days  
2310     Ft. from S Section Line  
4290     Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 32 TWP 13s RGE. 19w(E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY Ellis  
PHONE # (316 ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 7/11/52  
Character of Well (Oil) Gas, D&A, SWD, Input, Water Supply Well Plugging commenced 3/31/04  
Plugging Completed 3/31/04

The plugging proposal was approved on 3/31/04 (date)  
by Jay Pfeifer w/KCC in Hays, KS (KCC District Agent's Name).

Is ACO-1 filed?     If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3801 Bottom 3813 TD3818     Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	Surface	254	10 3/4	254	0
	Production	Surface	380	7	380	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set.

Plugged well as follows:

High Plains Machine cut off 5 1/2" csg head & welded on 5 1/2" slip collar. TIH w/122 jts 2 3/8" tbg = 3720', RU Allied Cementing, hook up to 10 3/4" surface csg mix & pumped 10 sks 60/40 10% gel. Pres to 1500#. Hooked up to 2 3/8" tbg mix & pumped 28 sks gel spacer, follow with 50 sks 60/40 10% gel w/200# hulls, pull tbg to 1550'. Mix & pump 100 sks w/300# hulls circ cmt to surface. TOH w/tbg. Top off 5 1/2" csg w/ 15 sks & pres 5 1/2" to 700# ISIP 500#, job complete @ 2:30 pm. Witnessed by Jay Pfeifer w/KCC in Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606  
Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 6<sup>th</sup> day of April, 2004

Notary Public - Kristin Grady

My Commission Expires: 2/06/08

Form CP-4 Revised 05-88



*[Handwritten signature]*

# ALLIED CEMENTING CO., INC.

17004

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
Russell

DATE <u>3/31/04</u>	SEC.	TWP.	RANGE	CALLED OUT <u>7:00 AM</u>	ON LOCATION <u>10:15 AM</u>	JOB START	JOB FINISH <u>2:30 PM</u>
LEASE <u>Riedel</u>	WELL# <u>11</u>	LOCATION <u>HAYS 7W GCRD 26W1W</u>			COUNTY <u>Ellis</u>	STATE <u>Kn</u>	

OLD OR NEW (Circle one)

CONTRACTOR MURFIN

TYPE OF JOB Plug

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH \_\_\_\_\_

TUBING SIZE 2 3/8 DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_

CEMENT AMOUNT ORDERED \_\_\_\_\_

275 64/40 10  
280 lb Gel Used 175 lb 500 # Hulls

COMMON	<u>105</u>	@	<u>7.15</u>	<u>750.75</u>
POZMIX	<u>70</u>	@	<u>3.80</u>	<u>266.00</u>
GEL	<u>40</u>	@	<u>10.00</u>	<u>400.00</u>
CHLORIDE		@		
ASC		@		
<u>Hulls</u>	<u>5</u>	@	<u>18.00</u>	<u>90.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Bill

# 221 HELPER SHANE

BULK TRUCK

# 362 DRIVER CKAY

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

RECEIVED

APR 07 2004

KCC WICHITA

HANDLING	<u>270</u>	@	<u>1.15</u>	<u>310.50</u>
MILEAGE	<u>54 / SK / MIE</u>			<u>472.50</u>
TOTAL				<u>2289.75</u>

REMARKS:

Tubing c 3800 split 280 lb gel  
Follow w/ 50 lb cont. w/ 200 # Hulls  
pull to 1550' Circ cement w/ 100 lb  
w/ 300 # Hulls  
pump down stw 1500' 700 # max  
500 # SHUT IN  
pump down Ann w/ 10 lb pres to 1500'

CHARGE TO: MURFIN

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Mark Pollock

SERVICE

DEPTH OF JOB	_____			
PUMP TRUCK CHARGE				<u>475.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>35</u>	@	<u>3.50</u>	<u>122.50</u>
TOTAL				<u>597.50</u>

PLUG & FLOAT EQUIPMENT

MANIFOLD	_____	@		
	_____	@		
	_____	@		
	_____	@		
	_____	@		
TOTAL				_____

TAX \_\_\_\_\_

TOTAL CHARGE \_\_\_\_\_

DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

PRINTED NAME \_\_\_\_\_